

JC13 Receill/ITO 2.5 MAR: 2002 EXPRESS MAIL LABEL NO. EV004939544US

ATTORNEY'S DOCKET NUMBER FORM PTO-1390 U.S. DEPARTMENT OF COMMERCE PATENT AND TRADEMARK OFFICE REN-13087 TRANSMITTAL LETTER TO THE UNITED STATES DESIGNATED/ELECTED OFFICE (DO/EO/US) U.S. APPLICATION NO. (If known, see 37 CFR 1.5) CONCERNING A FILING UNDER 35 U.S.C. 371 INTERNATIONAL APPLICATION NO. INTERNATIONAL FILING DATE PRIORITY DATE CLAIMED PCT/EP00/09569 29 September 2000 1 October 1999 TITLE OF INVENTION Device For The Carrying Out Of Chemical Or Biological Reactions APPLICANT(S) FOR DO/EO/US Wolfgang Heimberg, Markus Schurf, Thomas Herrmann, Matthias Knulle, Tilmann Wagner Applicant herewith submits to the United States Designated/Elected Office (DO/E O/US) the following items and other information: 1 X This is a FIRST submission of items concerning a filing under 35 U.S.C. 371. This is a SECOND or SUBSEQUENT submission of items concerning a filing under 35 U.S.C. 371. This is an express request to promptly begin national examination procedures (35 U.S.C. 371(f)). 3. **X** The US has been elected by the expiration of 19 months from the priority date (PCT Article 31). A copy of the International Application as filed (35 U.S.C. 371(c)(2)) is attached hereto (required only if not communicated by the International Bureau). has been communicated by the International Bureau. is not required, as the application was filed in the United States Receiving Office (RO/US). 6. **X** An English language translation of the International Application as filed (35 U.S.C. 371(c)(2)). Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371(c)(3)) are attached hereto (required only if not communicated by the International Bureau). have been communicated by the International Bureau. have not been made; however, the time limit for making such amendments has NOT expired. d. X have not been made and will not be made. An English language translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371(c)(3)). An oath or declaration of the inventor(s) (35 U.S.C. 371(c)(4)). An English language translation of the annexes to the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371(c)(5)). (Amendment to specification and claims) Items 11 to 16 below concern document(s) or information included: An Information Disclosure Statement under 37 CFR 1.97 and 1.98. An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.28 and 3.31 is included. 13. X A FIRST preliminary amendment. A SECOND or SUBSEQUENT preliminary amendment. A substitute specification. A change of power of attorney and/or address letter. Other items or information:

JC13 Recid POT/BTO 25 MAR 2002

U.S. AFFEICATION N.D. (I	J/0891361	NTERNATIONAL APPLICATION NO. PCT/EP00/0	9569		ATTORNEY'S DOC	N-13087
17. X The fol	llowing fees are submitted:			C	ALCULATIONS	
BASIC NATION Neither internation nor internation and Internation	NAL FEE (37 CFR 1.492 (a national preliminary examin onal search fee (37 CFR 1.40 pnal Search Report not prep	ation fee (37 CFR 1.482) 45(a)(2)) paid to USPTO ared by the EPO or JPO · · · · ·	\$1000.00			
USPTO but I	nternational Search Report p	e (37 CFR 1.482) not paid to prepared by the EPO or JPO				
International international	preliminary examination fee search fee (37 CFR 1.445(a	(37 CFR 1.482) not paid to USF (2)) paid to USPTO	PTO but \$710.00			
but all claims	did not satisfy provisions o	e paid to USPTO (37 CFR 1.48 of PCT Article 33(1)-(4)	\$690.00			•
International and all claims	s satisfied provisions of PCT	e paid to USPTO (37 CFR 1.48 Γ Article 33(1)-(4)	\$100.00			
	ENTER APPROF	PRIATE BASIC FEE AM	IOUNT =	\$	890.00	
Surcharge of \$130 months from the	0.00 for furnishing the oath earliest claimed priority dat	or declaration later than 26 26 27 CFR 1.492(e)).	0 30	\$		
CLAIMS	NUMBER FILED	NUMBER EXTRA	RATE			
Total claims	32 - 20 =	12	X \$18.00	\$	216.00	
Independent claims	1 -3 =	0	X \$80.00	\$	0.00	
MULTIPLE DEPE	ENDENT CLAIM(S) (if applica		+ \$270.00	\$		
		<u>DF ABOVE CALCULAT</u>		\$	1,106.00	
Applicant cl are reduced l	aims small entity status. by 1/2.	See 37 CFR 1.27. The fees in	ndicated above	\$		
		SUBT	OTAL =	\$	553.00	3.
Processing fee of months from the	\$130.00 for furnishing the learliest claimed priority date	English translation later than (37 CFR 1.492(f)).	20 30 +	\$		
		TOTAL NATIONA	ALFEE =	\$	553.00	
Fee for recording accompanied by a	the enclosed assignment (3) in appropriate cover sheet (3)	7 CFR 1.21(h)). The assignmer 37 CFR 3.28, 3.31). \$40.00 per	nt mus t be	\$		
		TOTAL FEES ENCI	LOSED =	\$	553.00	
			<u> </u>	Am	ount to be refunded:	\$
					charged:	Ψ
· .		to cover the above				
A duplic	narge my Deposit Account 1 ate copy of this sheet is encl	No in the a losed.	mount of \$		to cov	er the above fees.
c. X The Con overpayr	missioner is hereby authori nent to Deposit Account No	zed to charge any additional feature. A duplicate description of the second sec	es which may be copy of this she	requet is	nired, or credit a enclosed.	iny
NOTE: Where 1.137(a) or (b))	an appropriate time limit must be filed and granted	under 37 CFR 1.494 or 1.495 to restore the application to p	has not been m pendin g status.	iet, a	petition to rev	ive (37 CFR
SEND ALL CORRESE	PONDENCE TO:					·
Customer No			OTCALATE IN	E.		
	Porter & Clark LLP		SIGNATUR			1
700 Huntingt	-		Kennet	hA.	. Clark	
925 Euclid A			NAME			
Cieveland, Ol	hio 44115-1405		32,119			
			REGISTRAT	поп и	NUMBER	

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

#3/

In re application of

Group Art Unit

Wolfgang Heimberg et al.

Examiner

Serial No.

For:

Filed: March 25, 2002

Confirmation No.

DEVICE FOR THE CARRYING OUT OF :

PCT/EP00/09569

CHEMICAL OR BIOLOGICAL REACTIONS:

Filed 29 September 2000

U.S. National Filing of

Box PATENT APPLICATION Assistant Commissioner for Patents Washington, D.C. 20231

PRELIMINARY AMENDMENT

Dear Sir:

Prior to calculating the filing fee and examining the above noted application, please proceed to amend the application as follows:

In the Claims:

Please cancel pending claims 1-18 without prejudice.

Please add new claims 19-50 as follows:

19. Device for the carrying out of chemical or biological reactions with a reaction vessel receiving element for receiving a microtiter plate with several reaction vessels, wherein the reaction vessel receiving element has several recesses arranged in a regular pattern to receive the respective reaction vessels, a heating device for heating the reaction vessel receiving element, and a cooling device for cooling the reaction vessel receiving element, wherein a) the reaction vessel receiving element is divided into several segments, b) each segment is assigned a heating device, wherein the

heating devices may be actuated independently of one another, c) the individual segments are thermally decoupled in such a way that different temperature levels may be set and maintained in two adjacent segments.

- 20. Device according to claim 19, wherein each segment of the reaction vessel receiving element is assigned a cooling device, wherein the cooling devices may be actuated independently of one another.
- 21. Device according to claim 19, wherein the segments of the reaction vessel receiving element are each comprised of a base plate with one or more tubular, thin-walled reaction vessel holders, which form one piece together with the base plate.
- 22. Device according to claim 20, wherein the segments of the reaction vessel receiving element are each comprised of a base plate with one or more tubular, thin-walled reaction vessel holders, which form one piece together with the base plate.
- 23. Device according to claim 19, wherein the individual segments are thermally decoupled by means of an air gap formed between adjacent segments.
- 24. Device according to claim 22, wherein the individual segments are thermally decoupled by means of an air gap formed between adjacent segments.
- 25. Device according to claim 19, wherein the individual segments are thermally decoupled by means of a gap, formed between adjacent segments, in which a thermal insulator is inserted.
- 26. Device according to claim 24, wherein the individual segments are thermally decoupled by means of a gap, formed between adjacent segments, in which a thermal insulator is inserted.

- 27. Device according to claim 19, wherein each of the heating devices has a Peltier element, wherein each case one segment of the reaction vessel receiving element is assigned a Peltier element, and the Peltier elements are thermally coupled to the respective segments.
- 28. Device according to claim 26, wherein each of the heating devices has a Peltier element, wherein in each case one segment of the reaction vessel receiving element is assigned a Peltier element, and the Peltier elements are thermally coupled to the respective segments.
- 29. Device according to claim 19, wherein the cooling devices comprise a Peltier element and/or a heat exchanger, wherein in each case one segment of the reaction vessel receiving element is assigned a Peltier element and/or a heat exchanger.
- 30. Device according to claim 29, wherein the cooling devices comprise a Peltier element and/or a heat exchanger, wherein in each case one segment of the reaction vessel receiving element is assigned a Peltier element and/or heat exchanger.
- 31. Device according to claim 29, wherein the heat exchanger is provided with cooling ducts through which a fluid may flow, wherein the fluidic flow of individual heat exchangers may be controlled independently of one another.
- 32. Device according to claim 30, wherein the heat exchanger is provided with cooling ducts through which a fluid may flow, wherein the fluidic flow of individual heat exchangers may be controlled independently of one another.
- 33. Device according to claim 31, wherein that the fluid is a cooling fluid, in particular water.
- 34. Device according to claim 32, wherein that the fluid is a cooling fluid, in particular water.

- 35. Device according to claim 19, wherein the reaction vessel receiving element is divided into at least four segments.
- 36. Device according to claim 34, wherein the reaction vessel receiving element is divided into at least four segments.
- 37. Device according to claim 19, wherein the individual segments each have the same number of recesses.
- 38. Device according to claim 36, wherein the individual segments each have the same number of recesses.
- 39. Device according to claim 19, wherein on their side edges the segments have downwards-facing hook elements by which they rest on ties.
- 40. Device according to claim 38, wherein on their side edges the segments have downwards-facing hook elements by which they rest on ties.
- 41. Device according to claim 19, wherein each segment is assigned a temperature sensor with which the temperature of the segment concerned is sensed, with the temperature of the segment being controlled on the basis of the temperatures sensed by the individual sensors.
- 42. Device according to claim 40, wherein each segment is assigned a temperature sensor with which the temperature of the segment concerned is sensed, with the temperature of the segment being controlled on the basis of the temperatures sensed by the individual sensors.
- 43. Device according to claim 19, wherein each segment is assigned one or more temperature equalisation elements.
- 44. Device according to claim 42, wherein each segment is assigned one or more temperature equalisation elements.

- 45. Device according to claim 19, wherein it has a control unit to actuate the heating device and the cooling device, wherein the control unit is so designed that the cooling devices of the individual segments may be actuated individually.
- 46. Device according to claim 44, wherein it has a control unit to actuate the heating device and the cooling device, wherein the control unit is so designed that the cooling devices of the individual segments may be actuated individually.
- 47. Device according to claim 45, wherein in one operating mode the control unit actuates only a part of the segments, wherein the segments have side edges, and the segments adjoining the side edges of an actuated segment are not actuated.
- 48. Device according to claim 46, wherein in one operating mode the control unit actuates only a part of the segments, wherein the segments have side edges, and the segments adjoining the side edges of an actuated segment are not actuated.
- 49. Device according to claim 45, wherein in one operating mode the segments are so actuated that the temperature difference between adjacent segments is less than a predetermined temperature difference (ΔT).

50. Device according to claim 48, wherein in one operating mode the segments are so actuated that the temperature difference between adjacent segments is less than a predetermined temperature difference (ΔT).

Respectfully submitted,

RANKIN, HILL, PORTER & CLARK LLP

Kenneth A. Clark Reg. No. 32,119

925 Euclid Avenue Suite 700 Cleveland, Ohio 44115-1405 (216) 566-9700

10\ren\13087\pa\2

- EVUU47375440

JC13 Rec'd PCT/PTO 2 5 MAR 2002

10/089136

29/09/2000

Device for the carrying out of chemical or biological reactions 5

PCT/EP 00/09569

10

25

30

The present invention relates to a device for the carrying out of chemical or biological reactions with

a reaction vessel receiving element for receiving reaction vessels, wherein the reaction vessel receiving element has several recesses arranged in a regular pattern to receive reaction vessels, a heating device for heating the reaction vessel receiving element, and a cooling device for cooling the reaction vessel receiving element.

- Such devices are described as thermocyclers or thermocycling devices and are 15 used to generate specific temperature cycles, i.e. to set predetermined temperatures in the reaction vessels and to maintain predetermined intervals of time.
- A device of this kind is known from US 5,525,300. This device has four reaction 20 vessel receiving elements, each with recesses arranged in a regular pattern. The pattern of the recesses corresponds to a known pattern of reaction vessels of standard microtiter plates, so that microtiter plates with their reaction vessels may be inserted in the recesses.

The heating and cooling devices of a reaction vessel receiving element are so designed that a temperature gradient extending over the reaction vessel receiving element may be generated. This means that, during a temperature cycle, different temperatures may be obtained in the individual reaction vessels. This makes it possible to carry out certain experiments at different temperatures simultaneously.

5

10

15

30

This temperature gradient is used to determine the optimal denaturing temperature, the optimal annealing temperature and the optimal elongation temperature of a PCR reaction. To achieve this, the same reaction mixture is poured into the individual reaction vessels, and the temperature cycles necessary to perform the PCR reaction are executed. Such a temperature cycle comprises the heating of the reaction mixture to the denaturing temperature, which usually lies in the range 90°-95°C, cooling to the annealing temperature, which is usually in the range 40°-60°C, and heating to the elongation temperature, which is usually in the range 70-75°C. A cycle of this kind is repeated several times, leading to amplification of a predetermined DNA sequence.

Since a temperature gradient can be set, different but predetermined temperatures are set in the individual reaction vessels. After completion of the cycles it is possible to determine, with the aid of the reaction products, those temperatures at which the PCR reaction will give the user the optimal result. Here the result may be optimised e.g. in respect of product volume or also product quality.

The annealing temperature, at which the primer is added, has a powerful influence on the result. However the elongation temperature too can have beneficial or adverse effects on the result. At a higher elongation temperature, the addition of the bases is accelerated, with the probability of errors increasing with higher temperature. In addition, the life of the polymerase is shorter at a higher elongation temperature.

A thermocycling device, by which the temperature gradient may be set, makes it much easier to determine the desired temperatures, since a reaction mixture my simultaneously undergo cycles at different temperatures in a single thermocycling device.

5

10

15

20

25

30

3

Another important parameter for the success of a PCR reaction is the residence time at the individual temperatures for denaturing, annealing and elongation, and the rate of temperature change. With the known device, these parameters can not be varied in one test series for an individual reaction vessel holder. If it is desired to test different residence times and rates of change, this can be done in several test series either consecutively on one thermocycling device or simultaneously in several thermocycling devices.

For this purpose there are so-called multiblock thermocycling devices with several reaction vessel receiving elements, each provided with separate cooling, heating and control devices (see US 5,525,300). The reaction mixture to be tested must be distributed over several microtiter plates, for testing independently of one another.

To determine the optimal residence times and rates of temperature change it is necessary to have either several thermocycling devices or a multiblock thermocycling device, or to carry out tests in several consecutive test series. The acquisition of several thermocycling devices or of a multiblock thermocycling device is costly and the carrying-out of several consecutive test series takes too long. In addition, handling is laborious when only part of the reaction vessels of several microtiter plates is filled, with each of the latter being tested and optimised in separate test series. This is especially disadvantageous in the case of device which operate automatically and in which the reaction mixtures are subject to further operations, since several microtiter plates must then be handled separately. It is also extremely impractical when only part of the reaction vessels of the microtiter plates is filled, since the devices for further processing, such as e.g. sample combs for transferring the reaction products to an electrophoresis apparatus, are often laid out on the grid of the microtiter plates, which means that further processing is correspondingly limited if only part of the reaction vessels of the microtiter plate is used.

10

15

20

25

US 5,819842 discloses a device for the individual, controlled heating of several samples. This device has several flat heating elements arranged in a grid pattern on a work surface. Formed below the heating elements is a cooling device which extends over all the heating elements. In operation a specially designed sample plate is placed on the work surface. This sample plate has a grid plate, covered on the underside by a film. The samples are poured into the recesses of the grid plate. In this device the samples lie on the individual heating elements, separated from them only by the film. By this means, direct heat transfer is obtained. The drawback of this device, however, is that no commonly available microtiter plate can be used.

With increasing automation in biotechnology, thermocyclers are increasingly being used in automated production lines and with robots as one of several work stations. Here it is customary for the samples to be passed in microtiter plates from one work station to the next. If the device according to US 5,819,842 were to be used in such an automated production process, it would be necessary for the samples to be pipetted out of a microtiter plate into the specially designed sample plate before temperature adjustment, and from the sample plate into a microtiter plate after temperature adjustment. Here there is a risk of contamination of the samples. The use of this specially designed sample plate must therefore be regarded as extremely disadvantageous.

The invention is based on the problem of developing the device described above in such a way that the disadvantages described above are avoided and the parameters of the PCR process may be optimised with great flexibility.

To solve this problem the invention has the features specified in claim1. Advantageous developments thereof are set out in the additional claims.

The invention is characterised by the fact that the reaction vessel receiving element is divided into several segments, with the individual segments thermally

5

decoupled and each segment assigned a heating device which may be actuated independently.

By this means the individual segments of the device may be set to different temperatures independently of one another. This makes it possible not only to set different temperature levels in the segments, but also for them to be held for varying lengths of time or altered at different rates of change. The device according to the invention thus permits optimisation of all physical parameters critical for a PCR process, while the optimisation process may be carried out on a single reaction vessel receiving element in which a microtiter plate may be inserted.

With the device according to the invention it is therefore also possible to optimise the residence times and rates of temperature change without having to distribute the reaction mixture over different microtiter plates for this purpose.

The thermocycling device according to the invention is in particular suitable for optimising the multiplex PCR process, in which several different primers are used.

20

15

5

10

The above problem, and the features and advantages according to the present invention, may be better understood from the following detailed description of preferred embodiments of the present invention and with reference to the associated drawings.

25

The invention is explained in detail below with the aid of the drawings. These show in:

Fig. 1 a section through a device according to the invention for carrying out chemical or biological reactions in accordance with a first embodiment,

30

E	Fig. 2	a section through an area of a device according to the invention for carrying out chemical or biological reactions in accordance with a second embodiment,
5	Fig. 3	a schematic plan view of the device of Fig. 2,
	Fig. 4	a schematic plan view of a device according to a third embodiment
10	Fig. 5	an area of the device of Fig. 4 in a sectional view along the line A-A,
15	Figs. 6 to 9	schematic plan views of reaction vessel receiving elements with differing segmentation
10	Fig. 10	a clamping frame in plan view
20	Fig. 11	a device according to the invention in which segments of a reaction vessel receiving element are fixed by the clamping frame according to Fig. 10, and
	Fig. 12	a further embodiment of a device according to the invention in section, in which segments of a reaction vessel receiving element are fixed by the clamping frame according to Fig. 10.
25	•	s a first embodiment of the device 1 according to the invention for chemical or biological reactions in a schematic sectional view.

The device has a housing 2 with a bottom 3 and side walls 4. Located just above

and parallel to the bottom 3 is an intermediate wall 5, on which are formed

5

10

7

several bases 5a. In the embodiment shown in Fig. 1, a total of six bases 5a are provided, arranged in two rows of three bases 5a each.

Mounted on each of the bases 5a is a heat exchanger 6, a Peltier element 7 and a segment 8 of a reaction vessel receiving element 9. The heat exchanger 6 is part of a cooling device and the Peltier element 7 is part of a combined heating and cooling device. The elements (heat exchanger, Peltier element, segment) mounted on the bases 5a are bonded by an adhesive resin with good heat conducting properties, so that good heat transfer is realised between these elements, and the elements are also firmly connected to a segment element 10. the device has altogether six such segment elements 10. Instead of adhesive resin, a heat conducting film or a heat conducting paste may also be provided.

Each of the segments 8 of the reaction vessel receiving element 9 has a base plate 11 on which tubular, thin-walled reaction vessel holders 12 are integrally formed. In the embodiment depicted in Fig. 1, in each case 4 x 4 reaction vessel holders 12 are arranged on a base plate 11. The distance d between adjacent segments 8 is such that the reaction vessel holders 12 of all segments 8 are arranged in a regular pattern with constant grid spacing D. The grid spacing D is chosen so that s standardised microtiter plate with its reaction vessels may be inserted in the reaction vessel holders 12.

By providing the distance d between adjacent segments, an air gap which thermally decouples the segments 8 and segment elements 10 respectively is formed.

The reaction vessel holders 12 of the device shown in Fig. 1 form a grid with a total pf 96 reaction vessel holders, arranged in eight rows each with twelve reaction vessel holders 12.

5

10

15

25

30

8

The Peltier elements 7 are each connected electrically to a first control unit 13. Each of the heat exchangers 6 is connected via a separate cooling circuit 14 to a second control unit 15. The cooling medium used is for example water, which is cooled in the cool temperature control unit before transfer to one of the heat exchangers 6.

The first control unit 13 and the second control unit 15 are connected to a central control unit 16 which controls the temperature cycles to be implemented in the device. Inserted in each cooling circuit 14 is a control valve 19, which is controlled by the central control unit 16 to open or close the respective cooling circuit 14.

Pivotably attached to the housing 2 is a cover 17 in which additional heating elements 18 in the form of Peltier elements, heating films or semiconductor heating elements may be located. The heating elements 18 form cover heating elements, each assigned to a segment 8 and separately connected to the first control unit 13, so that each heating element 18 may be individually actuated.

The mode of operation of the device according to the invention is explained in detail below.

There are three modes of operation.

In the first operating mode all segments are set to the same temperature, i.e. the same temperature cycles are run on all segments. This operating mode corresponds to the operation of a conventional thermocycling device.

In the second operating mode the segments are actuated with different temperatures, wherein the temperatures are so controlled that the temperature difference ΔT of adjacent segments 8 is less than a predetermined value K which amounts for example to 5° -15°C. The value to be chosen for K depends on the

5

10

25

30

9

quality of the thermal decoupling. The better the thermal decoupling, the greater the value which can be chosen for K.

The temperature cycles input by the user may be distributed automatically by the central control unit 16 to the segments 8, so that the temperature differences between adjacent segments are kept as small as possible.

This second operating mode may be provided with a function by which the user inputs only a single temperature cycle or PCR cycle, and the central control unit 16 then varies this cycle automatically. The parameters to be varied, such as temperature, residence time or rate of temperature change, may be chosen by the user separately or in combination. Variation of the parameters is effected either by linear or sigmoidal distribution.

In the third operating mode, only part of the segments is actuated. In plan view (Fig. 3, Fig. 4, Figs. 6 to 9) the segments 8 have side edges 20. In this operating mode, the segments 8 adjacent to the side edges of an actuated segment 8 are not actuated. If the segments 8 themselves form a regular pattern (Fig. 3, Fig. 4, Fig. 6, Fig. 7 and Fig. 8), then the actuated segments are distributed in a
chessboard pattern. In the embodiments shown in Figs. 1 to 4, three of the six segments 8 can be actuated, namely the two outer segments of one row and the middle segment of the other row.

In this operating mode the actuated segments are not influenced by the other segments, and their temperature may be set completely independently of the other actuated segments. By this means it is possible to run quite different temperature cycles on the individual segments, with one of the segments for example heated up to the denaturing temperature and another held at the annealing temperature. Thus it is possible for the residence times, i.e. the intervals of time for which the denaturing temperature, the annealing temperature and the elongation temperature are held, also the rates of temperature change,

10

to be set as desired, and run simultaneously on the individual segments. In this way it is possible to optimise not only the temperatures, but also the residence times and the rates of temperature change.

In this operating mode it may be expedient to heat the non-actuated segments 8 a little, so that their temperature lies roughly in the range of the lowest temperature of the adjacent actuated segments. This avoids the non-actuated segments forming a heat sink for the actuated segments and affecting their temperature profile adversely.

10

30

A second embodiment of the device according to the invention is shown in Figs. 2 and 3. the basic design corresponds to that of Fig. 1, so that identical parts have been given the same reference number.

15 The second embodiment differs from the first embodiment by virtue of the fact that the side edges 20 of the segments 8 adjacent to the side walls 4 of the housing 2 engage in a slot 21 running round the inner face of the side walls 4, and are fixed therein for example by bonding. By this means the individual segment elements 10 are fixed in space, thereby ensuring that despite the form of the gaps between the segment elements 10, all reaction vessel holders 12 are arranged in the pattern of the reaction vessels of a microtiter plate. The side walls 4 of the housing 2 are made of a non heat conducting material. This embodiment may also be modified such that the slot 21 is introduced in a frame formed separately from the housing 2. The frame and the segments inserted in it form a part which may be handled separately during production and is bonded to the heating and cooling devices.

A third embodiment is shown schematically in Figs. 4 and 5. In this embodiment, ties 22 of non heat conducting material are located somewhat below the base plates 11 of the segments 8 in the areas between the segment elements 10 and between the segment elements 10 and the side walls 4 of the housing 2. On the

5

10

15

11

side edges 20 of the segments 8 and of the base plates 11 respectively are formed hook elements 23 which are bent downwards. These hook elements 23 engage in corresponding recesses of the ties 22 (Fig. 5), thereby fixing the segments 8 in their position. The hook elements 23 of adjacent segments 8 are offset relative to one another. The ties 22 thus form a grid, into eeach of the openings of which a segment 8 may be inserted.

This type of position fixing is very advantageous since the boundary areas between the segments 8 and the ties 22 are very small, so that heat transfer via the ties 22 is correspondingly low. Moreover this arrangement is easy to realise even in the confined space conditions between adjacent segment elements.

Shown in schematic plan view in Figs. 6 to 9 are reaction vessel receiving elements 9 which represent further modifications of the device according to the invention. In these reaction vessel receiving elements 9, the individual segments 8 are joined by webs 24 of a thermally insulating material joined to form a single unit The ties 22 are arranged between the side edges 20 of the base plates 11, to which they are fixed for example by bonding.

The segmentation of the reaction vessel receiving element of Fig. 6 corresponds to that of the first and second embodiment (Fig. 1-3), in which 4 x 4 reaction vessel holders are arranged on each segment 8.

The reaction vessel receiving element 9 shown in Fig. 7 is comprised of 24 segments 8 each with 4 \times 4 reaction vessel holders 12, while the segments 8 are in turn connected by means of thermally insulating webs 24.

In the reaction vessel receiving element 9 shown in Fig. 8, each segment 8 has only a single reaction vessel holder 12.

12

For the relatively finely sub-divided reaction vessel receiving elements 9 it is expedient to integrate temperature sensors in the thermocycling device. These temperature sensors sense the temperatures of the individual segments, so that the temperature of the segments 8 is regulated in a closed control loop on the basis of the temperature values determined by the temperature sensors.

Infrared sensors may for example be used as temperature sensors, located e.g. in the cover. With this sensor arrangement it is possible to sense the temperature of the reaction mixture directly.

10

15

5

Fig. 9 shows a reaction vessel receiving element 9 with six segments 8, rectangular in plan view, and a segment 8a in the form of a double cross formed by three intersecting rows of reaction vessel holders 12. The six rectangular segments 8 are each separated from the next rectangular segment by a row or column of reaction vessel holders. This segmentation is especially advantageous for the third operating mode described above, since the rectangular segments 8 are not in contact with one another and may therefore be actuated simultaneously as desired, with only the segment 8a in the form of a double cross not being actuated.

20

The segments 8 of the reaction vessel receiving element 9 are made from a metal with good heat conducting properties, e.g. aluminium. The materials described above as non-heat conducting materials or thermally insulating materials are either plastics or ceramics.

25

30

A further embodiment of the device according to the invention is shown in Fig. 11. In this embodiment the individual segments 8b of the reaction vessel receiving element 9 are fixed in position by means of a clamping frame 25 (Fig. 10).

5

10

15

20

25

30

The clamping frame 25 is grid-shaped and formed by longitudinal ties 26 and cross ties, wherein the ties 26, 27 span openings. Through these openings extend the reaction vessel holders 12 of the segments 8b. In the present embodiment, the ties 26, 27 are for instance in positive contact with the reaction vessel holders 12 and with the base plate 11 which protrudes from the reaction vessel holders. The 25 is provided with holes 28, through which pass bolts 29 for fixing the clamping frame to a thermocycling device 1.

Located below each of the segments 8b is a separately actuable Peltier element 7 and a cooling element 30 which extends over the area of all the segments 8b. Located in each case between the cooling element 30 and the Peltier element 7, and between the Peltier element 7 and the respective segment 8b is a heat conducting foil 31. The cooling element 30 is provided with holes through which extend the bolts 29, each fixed by a nut 32 to the side of the cooling element 30 facing away from the reaction vessel receiving element 9.

The clamping frame 25 is made from a non heat conducting material, in particular POM or polycarbonate. It therefore allows a fixing of the segments 8b of the reaction vessel receiving element 9 wherein the individual elements between the segments 8b and the cooling element 30 are under tension, thereby ensuring good heat transfer in the vertical direction between the individual elements. Since the clamping frame itself has poor heat conducting properties, the heat transfer between two adjacent segments 8b is kept low. For further reduction of heat transfer between two adjacent segments, the surfaces of the clamping frame 25 in contact with the segments 8b may be provided with narrow webs, so that in the areas adjoining the webs, air gaps are formed between the clamping frame 25 and the segments 8b.

In the embodiment shown in Fig. 11, a so-called heat pipe 33 is fitted between every two rows of reaction vessel holders 12. Such a heat pipe is distributed for example by the company THERMACORE INTERNATIONAL, Inc., USA. It is

14

comprised of a gastight jacket, in which there is only a small amount of fluid. The pressure in the heat pipe is so low that the fluid is in a state of equilibrium between the liquid and the gaseous aggregate state, and consequently evaporates at a warmer section of the heat pipe and condenses at a cooler section. By this means, the temperature between the individual sections is equalised. The fluid used is, for example, water or freon.

Through integration of such a heat pipe in the segments 8b of the reaction vessel receiving element 9, a temperature equalisation is effected over the segment 8b. By this means it is ensured that the same temperature is present over the whole segment 8b.

A further embodiment of the thermocycling device 1 according to the invention is shown in Fig. 12. The design of this thermocycling device 1 is similar to that of Fig. 11, therefore similar parts have been given the same reference numbers.

The segments 8c of this thermocycling device 1, however, have no heat pipe. Instead of heat pipes, a temperature equalisation plate 34 is provided in the area beneath each of the segments 8c. These temperature equalisation plates 34 are flat elements with a surface corresponding to the basic surface of one of the segments 8c. These temperature equalisation plates 34 are hollow bodies with a small amount of fluid, and work on the same principle as the heat pipes. By this means it is once again ensured that there are no temperature variations within a segment 8c.

25

30

5

10

15

20

The temperature equalisation plate may however be made from materials with very good heat conducting properties, such as e.g. copper. Additional heating and/or cooling elements, e.g. heating foils, heating coils or Peltier elements, may be integrated in such a temperature equalisation plate. The heating and cooling elements support homogeneity and permit more rapid heating and/or cooling

15

rates. A Peltier element, which generally does not have an even temperature distribution, is preferably combined with a flat heating element.

The invention is described above with the aid of embodiments with 96 recesses for receiving a microtiter plate with 96 reaction vessels. The invention is not however limited to this number of recesses. Thus for example the reaction vessel receiving element may also have 384 recesses to receive a corresponding microtiter plate. With regard to features of the invention not explained in detail above, express reference is made to the claims and the drawing.

In the embodiments described above, a cooling device with a fluid cooling medium is used. Within the scope of the invention it is also possible to use a gaseous cooling medium, in particular air cooling, instead of a fluid cooling

medium.

15

The reaction vessel receiving elements described above are comprised of a base plate with roughly tubular reaction vessel holders. Within the scope of the invention it is also possible to use a metal block, in which recesses to receive the reaction vessels of the microtiter plate are made.

16

List of References

	1	thermocycling device	25	clamping frame
	2	housing	26	longitudinal tie
5	3	bottom	27	cross tie
	4	side wall	28	hole
	5	intermediate wall	29	bolt
	5a	base	30	cooling element
	6	heat exchanger	31	heat conducting foil
10	7	Peltier element	32	nut
	8	segment	33	heat pipe
	8a	segment in the form of a	34	temperature equalisation plate
		double cross		
	9	reaction vessel receiving elemen	t	
15	10	segment element		
	11	base plate		
	12	reaction vessel holder		
	13	first control unit		
	14	cooling circuit		
20	15	second control unit		
	16	central control unit		
	17	cover		
	18	heating element		
	19	control valve		
25	20	side edge		
	21	slot		
	22	ties		
	23	hook element		
	24	web		

Patent Claims

- Device for the carrying out of chemical or biological reactions with
 a reaction vessel receiving element (9) for receiving a microtiter plate with
 several reaction vessels, wherein the reaction vessel receiving element (9) has
 several recesses arranged in a regular pattern to receive the respective reaction
 vessels,
- a heating device (7) for heating the reaction vessel receiving element (9), and a cooling device (6) for cooling the reaction vessel receiving element (9), characterised in that the reaction vessel receiving element (9) is divided into several segments (8), with the individual segments (8) thermally decoupled and each segment (8) assigned a heating device (7) which may be actuated independently of the others.
- Device according to claim 1,
 characterised in that
 each segment (8) of the reaction vessel receiving element (9) is assigned a
 cooling device (6), wherein the cooling devices (6) may be actuated independently of one another.
 - 3. Device according to claim 1 or 2, characterised in that the segments (8) of the reaction vessel receiving element (9) are each comprised of a base plate (11) with one or more tubular, thin-walled reaction vessel holders (12), which form one piece together with the base plate (11).
 - 4. Device according to any of claims 1 to 3, characterised in that

25

18

the individual segments (8) are thermally decoupled by means of an air gap formed between adjacent segments (8).

- 5. Device according to any of claims 1 to 3,
- 5 characterised in that the individual segments (8) are thermally decoupled by means of a gap, formed between adjacent segments (8), in which a thermal insulator is inserted.
 - 6. Device according to any of claims 1 to 5,
- characterised in that
 each of the heating devices has a Peltier element (7), wherein in each case one
 segment (8) of the reaction vessel receiving element (9) is assigned a Peltier
 element (7), and the Peltier elements (7) are thermally coupled to the respective
 segments (8).

15

20

25

- 7. Device according to any of claims 1 to 6, characterised in that the cooling devices comprise a Peltier element (7) and/or a heat exchanger (6), wherein in each case one segment (8) of the reaction vessel receiving element (9) is assigned a Peltier element (7) and/or a heat exchanger (6).
- 8. Device according to claim 7, characterised in that the heat exchanger (6) is provided with cooling ducts through which a fluid may flow, wherein the fluidic flow of individual heat exchangers (6) may be controlled independently of one another.
- Device according to claim 8,
 characterised in that
 that the fluid is a cooling fluid, in particular water.

19

10. Device according to any of claims 1 to 9,characterised in thatthe reaction vessel receiving element (9) is divided into at least four segments (8).

5

- 11. Device according to any of claims 1 to 10, characterised in that the individual segments (8) each have the same number of recesses.
- 10 12. Device according to any of the preceding claims, characterised in that on their side edges (20) the segments (8) have downwards-facing hook elements (23) by which they rest on ties 22.
- 13. Device according to any of claims 1 to 12, characterised in that each segment (8) is assigned a temperature sensor with which the temperature of the segment (8) concerned is sensed, with the temperature of the segment (8) being controlled on the basis of the temperatures sensed by the individual sensors.
 - 14. Device according to any of claims 1 to 13, characterised in that each segment (8b, 8c) is assigned one or more temperature equalisation elements (33, 34).
 - 15. Control unit to actuate the heating device and the cooling device of a device for the carrying out of chemical or biological reactions, which is designed according to any of claims 1 to 14,
- 30 characterised in that

20

the control unit (13, 16) is so designed that the heating devices (7) of the individual segments (8) may be actuated individually.

- 16. Control unit according to claim 15,
- 5 characterised in that the control unit (15, 16) is so designed that the cooling devices of the individual segments (8) may be actuated individually.
 - 17. Control unit according to claim 15 or 16,
- 10 characterised in that in one operating mode the control unit (13, 15, 16) actuates only a part of the segments, wherein the segments (8) have side edges (20), and the segments (8) adjoining the side edges (20) of an actuated segment (8) are not actuated.
- 15 18. Control unit according to any of claims 15 to 17, characterised in that in one operating mode the segments are so actuated that the temperature difference between adjacent segments (8) is less than a predetermined temperature difference (ΔT).

21

Summary

The invention relates to a device for the carrying out of chemical or biological reactions with a reaction vessel receiving element for receiving a microtiter plate with several reaction vessels, wherein the reaction vessel receiving element has several recesses arranged in a regular pattern to receive the respective reaction vessels, a heating device for heating the reaction vessel receiving element, and a cooling device for cooling the reaction vessel receiving element.

10

5


The invention is characterised by the fact that the reaction vessel receiving element is divided into several segments. The individual segments are thermally decoupled from one another, and each segment is assigned a heating device which may be actuated independently of the others.


15


20


By means of the segmentation of the reaction vessel receiving element, it is possible for zones to be set and held at different temperatures. Since the reaction vessel receiving element is suitable for receiving standard microtiter plates, the device according to the invention may be integrated in existing process sequences.


(Fig. 1)

























6/7







Please type a plus sign (+) inside ti	this box \rightarrow $+$			PT	O/SB/01 (10-00)			
Under the Paperwork Reduction Act of 1995	5, no persons are required	U.S. Patent a to respond to a collection of	and Trademark Office	c through 10/31/2002. (U.S. DEPARTMENT (OM8 0651-0032 OF COMMERCE			
		Attorney Docke	et Number	REN-13087				
DECLARATION FOR DESIGN		First Named In		Wolfgang Heimb	егд			
PATENT APPLIC		cc	COMPLETE IF KNOWN					
(37 CFR 1.6		Application Nur	nber	10 / 089136				
11. 51. 41. 52.	,	Filing Date		25 March 2002				
Submitted OR	Declaration Submitted after Initial	Group Art Unit						
Filing	Filing (surcharge (37 CFR 1.16 (e)) required)	Examiner Name	e		J			
·								
As a below named inventor, I here My residence, mailing address, and I believe I am the original, first and s names are listed below) of the subje	citizenship are as state sole inventor (if only one	e name is listed below)	or an original, first	l and joint inventor (if ne invention antitled:	i plural			
Device For 1	The Carrying Out Of	Chemical Or Biolog	gical Reactions					
the specification of which is attached hereto OR was filed on (MM/DD/YYYY) Application Number 10/089 I hereby state that I have reviewed amended by any amendment specific part applications, material informational filing date of the company and the company and the company and the company and the company applications.	03/25/2002 136 and was an and understand the corporation which is maintain which is maintain which became avecontinuation-in-part app	mended on (MM/DD/YY ntents of the above ide e. eterial to patentability a railable between the filinalication.	YY) ntified specifications defined in 37 CF and date of the prior	n, including the claim R 1.56, including for r application and the	licable). ns, as continuation- national or			
I hereby claim foreign priority bene certificate, or 365(a) of any PCT in America, listed below and have a certificate, or any PCT international	iternational application t also identified below b	which designated at le	ast one country of any foreion apolic	ther than the United ation for patent or	States of inventor's			
Prior Foreign Application Number(s)	Country	Foreign Filing Date (MM/DD/YYYY)	Priority Not Claimed	Certified Copy A YES	ttached? NO			
29917313.5 PCT/EP00/09569	Germany Europe	10/01/1999 09/29/2000	0.000		X X 			
☐ Additional foreign application n	umbers are listed on a	supplemental priority d	ata sheet PTO/SE	/02B attached heret	0:			
I hereby claim the benefit under 3	35 U.S.C. 119(e) of any	y United States provisio	onal application(s)	listed below.				
Application Number(s)	Filing Date	e (MM/DD/YYYY)	numbers supplem	al provisional applica s are listed on a nental priority data sh /02B attached herete	neet			

[Page 1 of 2]
Burden Hour Statement: This form is estimated to take 21 minutes to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sent to the Chief Information Officer. U.S. Patent and Trademark Office, Washington, OC 20231. DO NOT SEND FEES OR COMPLETED, FORMS TO THIS ADDRESS, SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.

Please type a plus sign (4) inside this box (+)

PTO/S8/01 (10-00) Approved for use through 10/31/2002. OMB 0651-0032 U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

DECLARATION — Utility or Design Patent Application Customer Number Direct all correspondence to: X **Q**07609_ OR 🗌 or Bar Code Label Correspondence address below Name Rankin, Hill, Porter & Clark LLP 925 Euclid Avenue, Suite 700 Address Address Cleveland Ohio 44115-1405 City ZIP U.S.A. (216) 566-9700 (216) 566-9711 Country Telephone I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false reactions and the like so made are punishable by fine or imprisonment, or both, under 18 U.S.C. 1001 and that such willful false statement may jeopardize the validity of the application or any patent issued thereon. ☐ A petition has been NAME OF SOLE OR FIRST INVENTOR: His unsigned inventor Given Name Family Name Wolfgang (first and middle [if any]) Heimberg or Surname Inventor's SeoS .01.1k Signature Ebersberg DE Residence: City Gennan Bohmerwaldstr, 72 Mailing Address Mailing Address Ebersberg 85560 'Germany **State** NAME OF SECOND INVENTOR: A petition has been the aris unsigned inventor Given Name Family Name Thomas Herrmann (first and middle [if any]) or Surname Inventor's 1.10,2002 Signature Country DE Ottobrunn Citizenship German Residence: City Putzbrunner Strasse 40a Mailing Address Mailing Address City Ottobrunn ZIP \$5521 Country Germany State

Please type a plus sign (+) inside this box ->	+	

PTO/SB/02A (3-97)

Approved for use through 9/30/98. OMB 0551-0032 ,

Palent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

DECLARATION

ADDITIONAL INVENTOR(S) Supplemental Sheet

Name of Addition	Name of Additional Joint Inventor, if any: A petition has this unsigned inventor									
Given Nar	me (first and middle [If any])			Family Name or Surname						
	<u>Matthias</u>	1	0	Knulle						
Inventor's Signature	X M. l.	us.	ll	-				Date	>	18.M. 2002
Residence: City	Grafing	State	DEK	ر ا	ountry	Germany		Citizons	hip	German
Post Office Address	Dietrich Bonhooffe	er Stra	isse 4							
Post Office Address										
City	Grafing	State			ZIP	85567		Ge	rman	y
Name of Addition	nal Joint Inventor, if any	<u>/:</u>			A petitio	on has to	d;	s unsig	ned in	ventor
Given Na	me (first and middle [if any])			Family Name or Surname						
	Markus			Schurf						
Inventor's Signature	X		- //:		·			Da	te	X
Residence: City	Siegsdorf	State			Country	Germany		Citize	nship	German
Post Office Address	Bergstrasse 31									
Post Office Address										
City	Siegsdorf	State			ZIP	83313	Count	ry (Gem	ıan
Name of Addition	nal Joint Inventor, if any	/:			A petitic	on ha: 🦽 Me	d for this	s unsig	ned in	ventor
Given Na	me (first and middle [if any])				Family Nor	nc or Si	umame		
	Tilmann					W	'agner	•		
Inventor's Signature	\times	_						Da	to	+
Residence: City	Grafing	State		,	Country	Germany		Citize	nship	German
Post Office Address	Am Seeschneidfel	d l								
Post Office Address	Post Office Address									
City	Grafing	State			ŽΙΡ	85567	Co	ountry	Ge	rmany

Burden Hour Statement: This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sent to the Chief Information Officer, Patent and Trademark Office, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.



Please type a plus sign (+) inside this box ->	[+]	
7,,,,,,,,,, -	1 . 1	

PTO/SB/02A (3-97)

sign (+) inside this box -> + Approved for use through 9/30/98. OMB 0651-0032

Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number valid OMB control number.

ADDITIONAL INVENTOR(S) DECLARATION Supplemental Sheet Name of Additional Joint Inventor, if any: A petition has ... this unslaned inventor Given Name (first and middle [if any]) Lawily Name or Surname Knulle Matthias Inventor's Signature Date Grafing German Germany Residence: City Citizenship Countr Dietrich Bonhoeffer Strasse 4 Post Office Address Post Office Address Grafing 85567 Germany City State ZIP Name of Additional Joint Inventor, if any: A petition has la as unsigned inventor Given Name (first and middle [if any]) Tomily Name or Surname Markus Schurf Inventor's *X*2002 Signature Date Siegsdorf DEX Germany German Citizenship Residence: City Bergstrasse 31 Post Office Address Post Office Address Siegsdorf 83313 German City State ZIP Country Name of Additional Joint Inventor, if any: A petition hav in field for this unsigned inventor Given Name (first and middle [if any]) Family Name or Surname Tilmann Wagner Inventor's Signature Date Grafing Germany German Citizenship Residence: City State Country Am Seeschneidfeld 1 Post Office Address Post Office Address Grafing 85567 Germany Country ZIP State

Burden Hour Statement: This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sent to the Chief Information Officer, Patent and Trademark Officer, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.

4-00

	$\overline{}$	ı
Please type a plus sign (+) inside this box ->	1 + 1	l
		ı

PTO/SB/02A (3-97)
sign (+) inside this box -> + Approved for use through 9/30/98, OMB 0651-0032
Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

DECLARATION				Supplemental Sheet							
Name of Addition	nal Joint Inventor, if a	any:			petitlo	n has	- / thi	s unsign	ed in	ventor	
Given Na	me (first and middle (if a	ny])		La⊸ily Na∷le or Sumame							
•	Matthias	•				K	nulle				
Inventor's . Signature	\times							Date)	<	
Residence: City	Grafing	State		co	untry	Germany		Citizensh	īρ	German	
Post Office Address	Dietrich Bonhoeffer Strasse 4										
Post Office Address											
City	Grafing	State		z	ЭР	85567		Ger	man	y	
Name of Addition	nal Joint Inventor, if a	зпу:	•	<u> </u>	petitio	n has 🐎	A	s unsign	ed in	ventor	
Given Na	me (first and middle [if a	ny])				Family Nav	e or S	urname			
	Markus					•	Schur	f			
Inventor's Signature	X						D at	Date X			
Residence: City	Siegsdorf	State		Co	untry	Germany		Citizen	ship	German	
Post Office Address	Bergstrasse 31		-								
Post Office Address											
City	Siegsdorf	State			ZIP	83313	Count	ry C	Gern	ıan	
Name of Addition	nal Joint Inventor, if a	any:		□ A	petitio	n ha∈ i∕n iile	d for thi	s unsign	ed in	ventor	
Given Na	me (first and middle [if a	ny])				Family Nar	ne or S	umame			
	Tilmann					W	agner/				
Inventor's Signature	× Te L	<u></u>						Dat	9	X41/26/	
Residence: City	Grafing	State	DES	کر د	untry	Germany		Citizen	ship	German	
Post Office Address	Am Seeschneid	feld l									
Post Office Address											
City	Grafing	State			ŽΙΡ	85567	Co	untry	Ge	rmany	

Burden Hour Statement: This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sont to the Chief Information Officer. Patent and Trademark Office, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.